BRUHAT BANGALORE MAHANAGARA PALIKE

Item No. 31

SCHEDULE - B

Name of Work:-Improvements of cross Roads and Drains at Venkatagiri Layout in ward no:10.

Sl. No.	Approved Qty.	Description	Unit	Approved Rates	
				In Figures	In Words
1	1550.00	KSRRB 300-45:Scarifying stone metal crust 50mm to 100mm thick with pick axes along with premix carpet/surface dressing and stacking of old serviceable materials within a lead of 100 meters by manual means including cost of all labour charges complete as per specifications. MORTH chapter 3, No. 156/ Item No. 19.51/ PWD SR 2012-13	Sqm	37.69	Rupees Thirty Seven And Paise Sixty Nine Only
2	313.88	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2012-13	Cum	117.89	Rupees One Hundred Seventeen And Paise Eighty Nine Only
3	313.88	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 167/ Item No. 20.18/ PWD SR 2012-13	Cum	1112.03	Rupees One Thousand One Hundred Twelve And Paise Three Only
4	2092.50	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5. No. 172/ Item No. 21.2/ PWD SR 2012-13	Sqm	2.50	Rupees Two And Paise Fifty Only
5	2092.50	KSRRB M500-6: Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH specification NO. 502, No. 172/ Item No. 21.6/ PWD SR 2012-13	Sqm	41.61	Rupees Forty One And Paise Sixty One Only

Sl. No.	Approved Qty.	Description	Unit	Approved Rates	
				In Figures	In Words
6	52.31	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications.25-30mm compacted thikness with 5% Birumen80/100grade (gradingII) P.No. 174/ Item No. 21.20.1/ PWD SR 2012-13	Cum	9266.92	Rupees Nine Thousand Two Hundred Sixty Six And Paise Ninety Two Only
7	313.88	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 7.00 Km	Cum	84.09	Rupees Eighty Four And Paise Nine Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92